

[www.blowerdoor.de](http://www.blowerdoor.de)

## Blower Door Measurements (EN 13829) and Results of 5 large Buildings - with one or more Blower Systems

Sigrig Dorschky, Paul Simons, Stefanie Rolfsmeier  
Certified Testers of Airtightness  
BlowerDoor GmbH • Energie- und Umweltzentrum  
D-31832 Springe • Germany

**BlowerDoor GmbH**  
Measuring Systems for Airtightness  
[www.blowerdoor.de](http://www.blowerdoor.de)



Im Energie- und Umweltzentrum  
31832 Springe-Eldagsen  
Telefon (0 50 44) 9 75-40  
Telefon 0700/BLOWERDOOR  
Telefax (0 50 44) 9 75-66  
e-mail: [BlowerDoor@t-online.de](mailto:BlowerDoor@t-online.de)  
Internet: [www.blowerdoor.de](http://www.blowerdoor.de)

BDM-Large Buildings F1 8-2006

© Sigrig Dorschky

Ingenieurgesellschaft  
Bau+ Energie+ Umwelt GmbH

[www.blowerdoor.de](http://www.blowerdoor.de)

**BlowerDoor GmbH**  
MessSysteme für Luftdichtheit  
[www.blowerdoor.de](http://www.blowerdoor.de)

## Introduction

**In Germany the blower door system has been used to measure the air tightness of**

- single-family houses since 1989,
- apartment buildings (multiple dwellings) since 1991,
- large administration and industrial buildings since 2002

**Proof of airtightness was required in**

- Low Energy House Standards  
(in some German countries, beginning in 1989)
- DIN 4108-7 (1996 and 2001)
- Energy Saving Directive EnEV (2002)

**Reasons and objectives:**

- saving energy
- guarantee effective function of the ventilation system
- avoidance of convection-related building damage
- protection against allergens in the home



- quality assurance
- sealing of clean rooms
- fire protection

BDM-Large Buildings F2 8-2006

© Sigrig Dorschky

Ingenieurgesellschaft  
Bau+ Energie+ Umwelt GmbH

### Level of air tightness required in accordance with EN 13829 (2000)

#### Airtightness specification (EnEV, DIN 4108-7):

air change rate per hour at a 50 Pa pressure difference:  
 $n_{50}$  = air leakage rate at 50 Pa / internal volume

*buildings with natural ventilation:*

$$n_{50, max} = 3 \text{ h}^{-1}$$

*buildings with mechanical ventilation systems:*

$$n_{50, max} = 1.5 \text{ h}^{-1}$$

#### Additional specification (DIN 4108-7):

air permeability at 50 Pa:

$q_{50}$  = air leakage rate at 50 Pa  $V_{50}$  / envelope area  $A_E$

*all buildings*

$$q_{50, max} = 3 \text{ m}^3/(\text{h} \cdot \text{m}^2)$$

#### Level of air tightness required for passive houses:

(PHI - Passiv Haus Institut, Darmstadt, Dr. Wolfgang Feist)

$$n_{50, max} = 0.6 \text{ h}^{-1}$$

### Methodology

We were commissioned to carry out a blower door measurement in accordance with EN 13829 and to determine the  $n_{50}$  (air change rate per hour at a 50 Pa pressure difference).

The tests were carried out with 1- 7 Minneapolis Blower Door units (model 3, 4).

#### The number of blower door systems required was determined as follows:

Allowed air flow rate at 50 Pa = Volume x  $n_{50, max}$ .

Nº. of blower systems = allowed air flow at 50 Pa / max. blower door capacity

#### Example – Building A (uncorrected volume advised by the client):

$$35,000 \text{ m}^3 \times 1.5 \text{ h}^{-1} = 52,500 \text{ m}^3/\text{h}$$

$$52,500 \text{ m}^3/\text{h} / 7,200 \text{ m}^3/\text{h} \text{ at } 50 \text{ Pa} = 7.3 \text{ blower door systems}$$

(If the building is leakier than planned, i.e. the  $n_{50, max}$  figure is exceeded, the 50 Pa pressure difference cannot be created with the calculated number of fans.)

Some of the buildings were more tight than planned: a number of fans could be switched off and closed after completed preparation of the building (i.e. shut all windows.)

### Example, Building A: Care Centre in Karlsruhe, Baden-Württemberg

built 2004,  
proof of tightness required  
in accordance with EnEV 2002  
(building with ventilation system):

$n_{50 \text{ max.}} = 1.5 \text{ h}^{-1}$

Volume (internal): 27,400 m<sup>3</sup>

**7 blower door systems installed**

#### Results:

Measured air flow rate:

45,111 m<sup>3</sup> / h

$n_{50} = 1.6 \text{ h}^{-1}$



Proof of tightness in accordance with EnEV not achieved: built using traditional methods of construction without special regard for air tightness.

### Building A: Installation of 5 blower door units


**External view of building A,  
installation of 5 (out of 7)  
blower door systems:**

Either 2 or 3 units were installed  
per external door opening using  
an aluminium frame and special  
panels (2 or 3-hole panels).



If internal doors create a pressure drop within the building, the blower systems have to be distributed around the building shell. The measurement then has to be carried out by a number of people who can communicate with each other by mobile phone. In other cases, the blower door systems can be installed at a single point and operated by just one person.


**Building A, in detail : Installation of 3 blower door units in one external door**



**Internal and external view:**

aluminium frame with 2 middle cross bars; 3 blower door units (open, without reducing rings); ((APT 8 - Automated Performance Testing system in case; notebook with TECLOG and BlowerDoor plus))

**Building A: pressure difference sequence (software TECLOG)**



measurements of zero-flow and indoor-outdoor pressure difference -65 until -30 Pa / fan pressure difference

Blower door		Building A: results of depressurization (software BlowerDoor plus)								Calculated fan pressure and air leakage rate of all 7 fans	
Number		1	2	3	4	5	6	7	8		
Model:	3 or 4	4	4	4	3	4	4	4			
Fan	0, A, B, C, D, E	0	0	0	0	0	0	0			
Configuration:											
Fan Configuration coefficient:	C [m³/hPa]	682.73	682.73	682.73	818.24	682.73	682.73	682.73			
Fan Configuration exponent:	n	0.4993	0.4993	0.4993	0.4947	0.4993	0.4993	0.4993			
Readings		Readings								Summary	
Building	BlowerDoor									V <sub>Fan</sub>	ΔP <sub>Fan</sub>
zero flow	-4.7	--	--	--	--	--	--	--	--	--	--
ΔP <sub>0</sub>											
ΔP <sub>1</sub> [Pa]	-64.4	ΔP <sub>Fan,1</sub> [Pa]	108.6	102.4	102.0	98.1	101.5	94.0	98.0	--	--
	--	V <sub>Fan,1</sub> [m³/h]	7091.5	6886.4	6872.9	7909.7	6856.1	6598.3	6737.0	48952	5202.9
ΔP <sub>2</sub> [Pa]	-53.7	ΔP <sub>Fan,2</sub> [Pa]	102.1	86.4	70.5	52.3	74.9	99.2	101.9	--	--
	--	V <sub>Fan,2</sub> [m³/h]	6876.3	6326.3	5715.4	5794.6	5890.8	6778.1	6869.6	44251	4250.4
ΔP <sub>3</sub> [Pa]	-57.1	ΔP <sub>Fan,3</sub> [Pa]	89.1	82.9	85.3	84.5	94.3	97.1	94.4	--	--
	--	V <sub>Fan,3</sub> [m³/h]	6424.3	6197.0	6286.0	7346.8	6608.8	6706.1	6612.3	46181	4629.8
ΔP <sub>4</sub> [Pa]	-47.5	ΔP <sub>Fan,4</sub> [Pa]	93.9	74.0	66.6	61.6	83.4	52.8	68.4	--	--
	--	V <sub>Fan,4</sub> [m³/h]	6594.8	5855.4	5555.3	6283.3	6215.7	4947.2	5629.8	41081	3662.5
ΔP <sub>5</sub> [Pa]	-35.7	ΔP <sub>Fan,5</sub> [Pa]	54.4	51.3	45.0	47.4	49.9	31.3	64.3	--	--
	--	V <sub>Fan,5</sub> [m³/h]	5021.5	4876.5	4567.7	5519.4	4809.6	3810.4	5458.7	34064	2516.8
ΔP <sub>6</sub> [Pa]	--	ΔP <sub>Fan,6</sub> [Pa]								0	0.0
	--	V <sub>Fan,6</sub> [m³/h]								0	0.0
ΔP <sub>7</sub> [Pa]	--	ΔP <sub>Fan,7</sub> [Pa]								0	0.0
	--	V <sub>Fan,7</sub> [m³/h]								0	0.0
ΔP <sub>8</sub> [Pa]	--	ΔP <sub>Fan,8</sub> [Pa]								0	0.0
	--	V <sub>Fan,8</sub> [m³/h]								0	0.0
zero flow	-4.5	--	--	--	--	--	--	--	--	--	--
ΔP <sub>0</sub>											

## Building B: Industrial building in Cloppenburg, Lower Saxony

built 2004,  
proof of tightness required  
to guarantee effective function  
of ventilation system:

$$n_{50 \text{ max.}} = 1.5 \text{ h}^{-1}$$

Volume (internal): 17,100 m³

**3 blower door systems installed**

**Results:**

Measured air flow rate:

22,260 m³ / h

$$n_{50} = 1.3 \text{ h}^{-1}$$



The building is used for producing special cables and is equipped with an ultramodern ventilation system. Adequate air tightness of the building envelope – as the precondition for correct performance of the ventilation system – could be successfully proved.

## Building C: Office building in Hamm, North Rhine-Westphalia

built 2003,  
quality assurance of the air barrier  
at the construction phase  
(building with natural ventilation):

$n_{50 \text{ max.}} = 3 \text{ h}^{-1}$

Volume (internal): 31,500 m<sup>3</sup>

3 blower door systems installed

### Results:

Measured air flow rate:

6,742 m<sup>3</sup> / h (1 blower door)

$n_{50} = 0.21 \text{ h}^{-1}$

measured with just one blower door unit, achieved excellent results – because of a very good air tightness design concept. The air tightness construction details were examined by the author at the design stage and suggestions for improvement were made.



## Building D: Industrial building in Brunswick, Lower Saxony

built 2002,  
proof of tightness required in accordance  
with passive house standard ("zero  
emission building", with ventilation system):

$n_{50 \text{ max.}} \leq 0.6 \text{ h}^{-1}$

Volume (internal): 46,500 m<sup>3</sup>

4 blower door systems installed

### Results:

Measured air flow rate:


10,089 m<sup>3</sup> / h (2 blower doors)

$n_{50} = 0.22 \text{ h}^{-1}$

A preliminary measurement of the air barrier was carried out during the construction phase because, besides the thermal insulation, the air tightness of the building is an essential factor in ensuring high energy efficiency. The planned ventilation with heat recovery can only achieve its aim if the air exchange for provision of the required clean, fresh air actually takes place via the heat exchanger and not through joints and cracks.



### Building D, in detail : Installation of 4 blower door units in two external doors



Following remedial works, two of the four blower door units could be switched off during the course of the measurement – the final measurement was carried out with just two blower door systems.

### Building E: Industrial warehouse in Marl, North Rhine-Westphalia

built 2004,  
proof of tightness for fire prevention  
system (by injection of nitrogen)  
required:

$$n_{50 \text{ max.}} \leq 0.02 \text{ h}^{-1}$$

Volume (internal): 191,000 m<sup>3</sup>,  
1 blower door installed

**Results:**


Measured air flow rate:  
2,613 m<sup>3</sup> / h (1 blower door, ring A)  
 $n_{50} = 0.014 \text{ h}^{-1}$



By injecting nitrogen, this system reduces the oxygen content in the warehouse to such an extent that a fire is no longer possible. As a result, no sprinkler system is required. Instead, under the terms of the contract, extremely demanding requirements are imposed with regard to air tightness (facade made from mineral fibre sandwich panels).

## Conclusion

**The Blower Door test should be included in any national regulation - for small dwelling houses as well as for large office buildings - then the quality will become high!**



And only airtight houses save energy because in good insulated buildings

**Losses by convection**  
(through joints and gaps)

**are bigger than**  
**Losses by heat transmission**  
(through walls and roofs)



**You are invited to our European BlowerDoor Symposium: 16+17.6.2006 in Freiburg!**